

Red Zone Cybersecurity Commissioning for Design & Construction Projects

Presented by: Nate McCarty

Panel: Antonio Jefferson, Joe Ellis, Charlie Weaver & Kevin Gaddist

11 Jan 2024



CIO Cybersecurity POCs



CYBERSECURITY PROGRAM OVERSIGHT

CIO2 CYBERSECURITY



CIO2: Joseph Ellis - 904-542-5839 Cybersecurity Division Director

3

CIO: Andrea Freeman Command Information Officer 904-542-4191

CIO4 OPERATIONAL TECHNOLOGY



CIO4: Charlie Weaver - 904-542-8482 Operational Technology Division Director



CIO21: Maria Lopez - 904-546-9060 RMF Team Lead Risk Management Framework (RMF) Requests for Authority-to-Operate (ATO)



CIOPM: Antonio Jefferson - 904-546-9056
Cybersecurity Contracts Program Manager
Red Zone Commissioning and BOD Support
Construction and Design Contracts Review



CIO41: Kevin Gaddist - 904-542-8495
OT Enterprise Support Branch Manager
Control System Platform Enclave (CSPE)
Continuous Monitoring Support



CIO42: Bobby Kelley- 904-542-2490
Control Systems Support Branch Manager
AMI, SCADA, DDC, and HVAC Support
Cyber Hygiene & Continuous Monitoring Support



CIO43: Paddy Jackson - 904-542-1384
Information Systems Security Engineer Team Lead
Cybersecurity Commissioning Support
Risk Management Framework (RMF) Support



CIO44: Keith Long- 904-542-8434
CyCx Team Lead
Cybersecurity Commissioning Support
Construction and Design Contracts Review

Red Zone Cybersecurity Commissioning for Design & Construction Projects

Red Zone Cybersecurity Commissioning (CyCx) is a method of evaluating whether the cybersecurity controls applied to a Facility Related Control System (FRCS) meet contract requirements using UFC and UFGS guides.


- **UFC 4-10-06** Cybersecurity for Facility Related Control System (FRCS)
- **UFGS 25-05-11** Guide Specification for Cybersecurity for FRCS



NAVFAC SE developed a **FRCS Cybersecurity Commissioning (CyCx) Checklist** derived from the UFGS 25-05-11 to track contract compliance.



Cybersecurity of Facility Related Control Systems: UFC 4-010-06




Update published 10-October-2023

Unified Facilities Criteria (UFC)

- Provides planning, design, construction, sustainment, restoration, and modernization criteria.
- Applies to the Military Departments, the Defense Agencies, and the DoD Field Activities
- Used for all DoD projects and work for other customers where appropriate
- Integrates only a subset of Risk Management Framework (RMF) requirements for facility-related control systems
- Applies to all new construction and repair projects
- Narrows RMF Focus to design only and not system life cycle
- 4-010-06 provides:
 - · Guidance to Designers-of-Record
 - · Information intended for Designers-of-Record
 - Cyber Impact Levels of Confidentiality, Integrity, & Availability (C-I-A) Guidance for impact rating
 - Detailed guidance for LOW and MODERATE impact systems

Naval Facilities Engineering Systems Command Navyal Facilities Engineering Systems Command Navyaco sourcess F


Cybersecurity of Facility Related Control Systems: UFGS 25 05 11



- Update published August 2023
 - Whole Building Design Guide (www.wbdg.org)
- Consolidated all cybersecurity submittals into one specification
- Includes requirements to submit for contractual fulfillment by implementing cybersecurity into facility related controlled systems construction projects
- Requires security control submittals to be properly answered



Red Zone Cybersecurity Commissioning For Facility-Related Control Systems






Cybersecurity Criteria Should Be Included In Contract Specifications




Red Zone Commissioning Process





Pre-Red Zone Commissioning Process





NAVFAC FRCS CyCx Checklist

- Based on the UFGS 25-05-11
- A technical snapshot of the FRCS CS readiness status
- Workbook consists of:
 - Instructions
 - CyCx Checklist Data
 - Required Submittals
 - Red Zone After Action Report

	Project or Work Order Number: Control System or Device/Component (Choose one):			
	Control System or Device/Component Name:			
	Date:			
	iction tab before completing this checklist. Contractor is to complete to			
	evels 2 - 5 of the UFC 04-01-06 Control System Architecture. NOTE:	If each devic	e type is identical and co	nfigured the same, only one sheet
quired.				
Task ID	Requirement	Reference	Status	Comments
		tor/Vendor		
C1	Have all unused accounts been deleted from control system?	AC-2		
C2	Have all shared credentials/accounts utilized on the control system been approved by the government. If not, provide explanation in	AC-2		
62	the comments.			
	Have all control system accounts been modified to the concept of	0.0020-007		
C3	least privileged; leaving only authorized user and services access	AC-6		
	required to meet the mission of the system?			
	Are there user initiated methods and/or mechanism to prevent	AC-11		
C4	unauthorized access to the control system when left unattended?			
C5	Has all sensets assess been assessed by the assessment?	AC 47		_
00	Has all remote access been approved by the government? Are all control system wireless network access configured with to	AC-17		_
C6	the DoD approved encryption standards? If not, provide	AC-18		
	explanation in comments?			
C7	Have control system logs have been reviewed and appropriate	AU-1		
O1	actions taken based on log content (i.e. alarms)?	V0-1		
0.0	Has the inventory of all physical devices and systems been	011.0		
C8	documented on a control system inventory and approved by the government?	CM-8		
2020.00	Has the inventory of all software and software licenses been	0.000000		
C9	documented and approved by the government?	CM-8		
Petito Kin	Have all default passwords been changed to meet the DoD	IA-5		
C10	password standards or set to the maximum strength allowable by	174-5		
	the operating system or firmware?	_		
	Are all physical access points to the control system and its components installed where monitored physical access			
C11	authorization controls are in place (i.e., CCTV, alarms, guards) or is	PE-3, PE-6		
0	properly secured (i.e., behind a locked door or enclosure)? If not,			
	provide explanation in comments.			
C12	Does the control system have long-term alternate power supply in	PE-11		
0.12	the event of an extended loss of the primary power source?			
C13	Have all control system parts and replacement components been verified as genuine and not been altered?	\$A-12		
	Has government approved installation of any components and	01.44		
C14	software approaching or at end of life support?	SA-22		
C15	Does the control system fail to a secure state in an event of a	SC-24		
	failure during system initialization, shutdown, and aborts?			
C16	Are all non-essential or unrequested functionalities, connection ports and input/output devices physically disabled or removed?	SC-41		
		ent Use Only		
	All privilege user have an approved Navy System Access	Unit Ode Olly		
04	Authorization Request (SAAR-N) on file documenting a proper	10.00		
G1	background investigation and completed privileged access	AC-6(5)		
-	agreement?			
00	All operator/technician(s) have an approved Navy System Access	47.0		
G2	Authorization Request (SAAR-N) on file documenting completion of annual Cyber Awareness Training.	AT-2		
	Has a Continuous Monitoring plan been documented, and if so, has			
	that Plan been implemented which focuses on, at a minimum, the			
G3	following core tasks: POA&M updates, patching, reporting,	CA-7		
50	configuration management (CM), log file analysis, account			
	management, firmware updates? (To include scanning when possible/applicable)			
	Have the operator/technician(s) been informed that changes to the			
G4	control system baseline may have a cybersecurity impact and	CM-2		
٠.	require coordination with CIO/N6/System Owner.	J		
	Has the Incident Response Plan (IRP) applicable to this control			
G5	system been updated for any unique requirements associated with	IR-1		
95	this control system? If so, provide explanation in the comments.	IR-1		
O.E	Has the Physical Security Officer and after-hours point of contract	MA E		
G6	of the control system space been documented? If not, document in the comments.	MA-5		





NAVFAC FRCS CyCx Checklist Example: Control Implementation Assessment

	NAVFAC FRCS Cybersecurity	Commiss	ioning (CyCx) Check	list
	Project or Work Order Number:			
	Control System or Device/Component (Choose one):			
	Control System or Device/Component Name:			
	Date:			
Read instru Setween Le Seguired.	uction tab before completing this checklist. Contractor is to complete to evels 2 - 5 of the UFC 04-01-08 Control System Architecture. NOTE :	his checklist fo If each devic	r each control system and/or c e type is identical and config	omponent. These devices will range ured the same, only one sheet
Task ID	Requirement	Reference	Status	Comments
		tor/Vendor		
C1	Have all unused accounts been deleted from control system?	AC-2		
C2	Have all shared credentials/accounts utilized on the control system been approved by the government. If not, provide explanation in the comments.	AC-2		
C3	Have all control system accounts been modified to the concept of least privileged; leaving only authorized user and services access required to meet the mission of the system?	AC-6		
C4	Are there user initiated methods and/or mechanism to prevent unauthorized access to the control system when left unattended?	AC-11		
C5	Has all remote access been approved by the government?	AC-17		
C6	Are all control system wireless network access configured with to the DoD approved encryption standards? If not, provide explanation in comments?	AC-18		
C7	Have control system logs have been reviewed and appropriate actions taken based on log content (i.e. alarms)?	AU-1		
C8	Has the inventory of all physical devices and systems been documented on a control system inventory and approved by the government?	CM-8		
C9	Has the inventory of all software and software licenses been documented and approved by the government?	CM-8		
C10	Have all default passwords been changed to meet the DoD password standards or set to the maximum strength allowable by the operating system or firmware?	IA-5		
C11	Are all physical access points to the control system and its components installed where monitored physical access authorization controls are in place (i.e., CCTV, alarms, guards) or is properly secured (i.e., behind a locked door or enclosure)? If not, provide explanation in comments.	PE-3, PE-6		
C12	Does the control system have long-term alternate power supply in the event of an extended loss of the primary power source?	PE-11		
C13	Have all control system parts and replacement components been verified as genuine and not been altered?	\$A-12		
C14	Has government approved installation of any components and software approaching or at end of life support?	SA-22		
C15	Does the control system fail to a secure state in an event of a failure during system initialization, shutdown, and aborts?	SC-24		
C16	Are all non-essential or unrequested functionalities, connection ports and input/output devices physically disabled or removed?	SC-41		
17		ent Use Only		
G1	All privilege user have an approved Navy System Access Authorization Request (SAAR-N) on file documenting a proper background investigation and completed privileged access agreement?	AC-6(5)		
G2	All operator/technician(s) have an approved Navy System Access Authorization Request (SAAR-N) on file documenting completion of annual Cyber Awareness Training.	AT-2		
G3	Has a Continuous Monitoring plan been documented, and if so, has that Plan been implemented which focuses on, at a minimum, the following core takes. POA&M updates, patching, reporting, configuration management (CM), log file analysis, account management, firmware updates? (To include scanning when possible/apolicable)	CA-7		
G4	Have the operator/technician(s) been informed that changes to the control system baseline may have a cybersecurity impact and require coordination with CIO/N6/System Owner.	CM-2		
G5	Has the Incident Response Plan (IRP) applicable to this control system been updated for any unique requirements associated with this control system? If so, provide explanation in the comments.	IR-1		
G6	Has the Physical Security Officer and after-hours point of contract of the control system space been documented? If not, document in the comments.	MA-5		

	NAVFAC FRCS Cybersecurity Project or Work Order Number:			126	
	Control System or Device/Component (Choose one):				
	Control System or Device/Component (Choose one):	LCS Facility DDC			
	Date:				
	uction tab before completing this checklist. Contractor is to complete to evels 2 - 5 of the UFC 04-01-06 Control System Architecture. NOTE:				
Task ID	Requirement	Reference	Status	Comments	
		ctor/Vendor			
C1	Have all unused accounts been deleted from control system?	AC-2	Compliant	No unused account present.	
C2	Have all shared credentials/accounts utilized on the control system been approved by the government. If not, provide explanation in	AC-2	Compliant	There are no shared accounts associated with the system	
	the comments. Have all control system accounts been modified to the concept of	AC-6		At this time there are only one acco	
C3	least privileged; leaving only authorized user and services access required to meet the mission of the system?		Compliant	for administrative purposes	
C4	Are there user initiated methods and/or mechanism to prevent unauthorized access to the control system when left unattended?	AC-11	Not Applicable	Requirement will be re-assessed for update to checklist.	
C5	Has all remote access been approved by the government?	AC-17	Compliant	There is remote access connectivit	
	Are all control system wireless network access configured with to		·	Wireless mechanism will be physical	
C6	the DoD approved encryption standards? If not, provide explanation in comments?	AC-18	Not Applicable	removed from JACE.	
C7	Have control system logs have been reviewed and appropriate actions taken based on log content (i.e. alarms)?	AU-1	Not Applicable	N/A at this time until fully operation	
C8	Has the inventory of all physical devices and systems been documented on a control system inventory and approved by the government?	CM-8	Compliant		
C9	Has the inventory of all software and software licenses been documented and approved by the government?	CM-8	Compliant		
C10	Have all default passwords been changed to meet the DoD password standards or set to the maximum strength allowable by the operating system or firmware?	IA-5	Not Applicable	At this time this security controls he not been implemented until full turnover.	
C11	Are all physical access points to the control system and its components installed where monitored physical access authorization controls are in place (i.e., CCTV, alarms, guards) or is properly secured (i.e., behind a locked door or enclosure)? If not, provide explanation in comments.	PE-3, PE-6	Compliant	CAC enabled readers for door lock- installed throughout the facility	
C12	Does the control system have long-term alternate power supply in the event of an extended loss of the primary power source?	PE-11	Not Applicable	CIO will determine if building gener will power building PLCs and other level 0 and 1 device.	
C13	Have all control system parts and replacement components been verified as genuine and not been altered?	SA-12	Not Applicable	Requirement will be re-assessed for update to checklist.	
C14	Has government approved installation of any components and software approaching or at end of life support?	SA-22	Not Applicable	End of life is 3 years or more away.	
C15	Does the control system fail to a secure state in an event of a failure during system initialization, shutdown, and aborts?	SC-24	Not Applicable	Besides for the laptop all other devi are programmable controllers	
C16	Are all non-essential or unrequested functionalities, connection ports and input/output devices physically disabled or removed?	SC-41	Compliant	There are no non-essential port connections	
		ent Use Only			
G1	All privilege user have an approved Navy System Access Authorization Request (SAAR-N) on file documenting a proper background investigation and completed privileged access agreement?	AC-6(5)	Not Applicable	Only 1 contractor account present. Upon turnover, contractor account removed and SAARs verified befor account creation.	
G2	All operator/technician(s) have an approved Navy System Access Authorization Request (SAAR-N) on file documenting completion of annual Cyber Awareness Training.	AT-2	Not Applicable	Only 1 contractor account present. Upon turnover, contractor account removed and SAARs verified befor account creation.	
G3	Has a Continuous Monitoring plan been documented, and if so, has that Plan been implemented which focuses on, at a minimum, the following core tasks: POA&M updates, patching, reporting, configuration management (Ni), log file analysis, account management, firmware updates? (To include scanning when possible/applicable)	CA-7	Not Applicable	This was just an assessment of a system without an ATO contract.	
G4	Have the operator/technician(s) been informed that changes to the control system baseline may have a cybersecurity impact and require coordination with CIO/N6/System Owner.	CM-2	Compliant	CIO provided change management training to BOSC COR and System Owner.	
G5	Has the Incident Response Plan (IRP) applicable to this control system been updated for any unique requirements associated with this control system? If so, provide explanation in the comments.	IR-1	Compliant	System will follow NS Mayport IRP follow NAVFAC SE CCIR.	
G6	Has the Physical Security Officer and after-hours point of contract of the control system space been documented? If not, document in the comments.	MA-5	Compliant	Information was collected by the CI OT ISSM	



NAVFAC FRCS CyCx Checklist Example: Submittals

	NAVFAC FRCS Cybersecurity Commissioning (CyCx) Checklist				
		ther Require		, cx, chesimot	
	Project or Work Order Number			-	
	••••				
	Control System or Device/Component (Choose one):			
	Control System or Device/Component Name	»:			
	Contractor is to complete this checklist for all FRC	S associated with	the project, refer	ence the instructions tab for guidance.	
Task ID	Requirement	Affected CCI /	Status	Comments	
Task ID	<u>'</u>	AP		Comments	
		Preconstruction	Submittals		
1	Wireless and Wired Broadcast Communication Request	AC-18			
2	Device Account Lock Exception Request	AC-7			
3	Multiple Ethernet Connection Device Request	PL-8			
4	Contractor Computer Cybersecurity Compliance Statements	PL-4			
5	Contractor Temporary Network Cybersecurity Compliance Statements	PL-4			
6	Cybersecurity Interconnection Schedule	PL-8			
7	Protection of Information At Rest Proposal	SC-28			
8	Proposed STIG and SRG Applicability Report	CM-2			
		SD-02 Shop Dra	wings		
1	Network Communication Report	CA-9, CM-6, CM-7, PL-8, SC-8, SC-41			
2	Cybersecurity Riser Diagram	PL-2, PL-8			
		SD-03 Product	Data		
1	Control System Cybersecurity Documentation	SA-5			
	· · · · · · · · · · · · · · · · · · ·	SD-06 Test Rep	orts		
1	Wireless Communication Test Report	AC-18			
2	Control System Cybersecurity Testing Procedures	RA-5			
3	Control System Cybersecurity Testing Report	RA-5			
3	Control System Cybersecurity Testing Report	RA-5	ates		
		SD-07 Certifica	ates		
	Software Licenses	SD-07 Certifica CM-10			
1	Software Licenses	SD-07 Certifica CM-10 0-11 Closeout Su			
1	Software Licenses SE	SD-07 Certifica CM-10 0-11 Closeout Su IA-5			
1 2	Software Licenses SE Confidential Password Report Password Change Summary Report	SD-07 Certifica CM-10 0-11 Closeout Su IA-5 IA-5			
1 2 3	Software Licenses Confidential Password Report Password Change Summary Report Enclosure Keys	SD-07 Certifica CM-10 D-11 Closeout Su IA-5 IA-5 PE-3			
1 2 3 4	Software Licenses SE Confidential Password Report Password Change Summary Report Enclosure Keys Software and Configuration Backups	SD-07 Certifica CM-10 D-11 Closeout Su IA-5 IA-5 PE-3 CP-10			
1 1 2 3 4 5	Software Licenses St Confidential Password Report Password Change Summary Report Enclosure Keys Software and Configuration Backups Auditing Front End Software	SD-07 Certifica CM-10 D-11 Closeout Su IA-5 IA-5 PE-3 CP-10 AU-3			
1 1 2 3 4 5	Software Licenses Confidential Password Report Password Change Summary Report Enclosure Keys Software and Configuration Backups Auditing Front End Software Device Audit Record Upload Software	SD-07 Certifica CM-10 0-11 Closeout Su IA-5 IA-5 PE-3 CP-10 AU-3 AU-3			
1 1 2 3 4 5 6 7	Software Licenses SE Confidential Password Report Password Change Summary Report Enclosure Keys Software and Configuration Backups Auditing Front End Software Device Audit Record Upload Software System Maintenance Tool Software	SD-07 Certifics CM-10 -11 Closeout Su IA-5 IA-5 PE-3 CP-10 AU-3 AU-3 MA-3			
1 1 2 3 4 5	Software Licenses Confidential Password Report Password Change Summary Report Enclosure Keys Software and Configuration Backups Auditing Front End Software Device Audit Record Upload Software System Maintenance Tool Software Control System Scanning Tools STIG, SRG and Vendor Guide Compliance Result	SD-07 Certifica CM-10 0-11 Closeout Su IA-5 IA-5 PE-3 CP-10 AU-3 AU-3			
1 2 3 4 5 6 7 8	Software Licenses Confidential Password Report Password Change Summary Report Enclosure Keys Software and Configuration Backups Auditing Front End Software Device Audit Record Upload Software System Maintenance Tool Software Control System Scanning Tools	SD-07 Certific:			
1 1 2 3 4 5 6 7 8 9	Software Licenses Confidential Password Report Password Change Summary Report Enclosure Keys Software and Configuration Backups Auditing Front End Software Device Audit Record Upload Software System Maintenance Tool Software Control System Scanning Tools STIG, SRG and Vendor Guide Compliance Result Report Control System Inventory Report	SD-07 Certifici CM-10			
1 1 2 3 4 5 6 7 8	Software Licenses Confidential Password Report Password Change Summary Report Enclosure Keys Software and Configuration Backups Auditing Front End Software Device Audit Record Upload Software System Maintenance Tool Software Control System Scanning Tools STIG, SRG and Vendor Guide Compliance Result Report	SD-07 Certific:	bmittals		

	NAVFAC FRCS Cyberse	curity Comr	nissioning (C	yCx) Checklist		
		her Require P426 LIT		T SHIP (LCS) SUPPORT FACILITY MAYPORT		
Project or Work Order Number:				CONTRACT: N69450-19-C-0913		
-	Control System or Device/Component (Choose one):	Control System				
	Control System or Device/Component Name:	P426 LITTORAL COMBAT SHIP (LCS) Direct Digital Control				
		S associated with the project, reference the instructions tab for guidance. Affected CCI / Section 1				
Task ID	Requirement	AP	Status	Comments		
	SD-01 F	Preconstruction	n Submittals			
1	Wireless and Wired Broadcast Communication Request	AC-18	Not Submitted	Updated 7/26/22: Initially marked NA due the contractor reporting no wireless communications requirement (See Submittal 347.02-25 05 11). Wireless communication was recently discovered. Gov't will remediate after BOD. Physical device will be removed.		
2	Device Account Lock Exception Request	AC-7	Not Applicable	Not Applicable		
3	Multiple Ethernet Connection Device Request	PL-8	Not Applicable	Not Applicable		
4	Contractor Computer Cybersecurity Compliance Statements	PL-4	Approved			
5	Contractor Temporary Network Cybersecurity Compliance Statements	PL-4	Approved			
6	Cybersecurity Interconnection Schedule	PL-8	Approved	Updated 7/26/22: Contractor provided submitta on 7/14/22. Wireless communication was not identified on schedule. Awaiting attachment 1 as stated on front page of submittal package dated 4/12/22.		
7	Protection of Information At Rest Proposal	SC-28	Not Applicable	Out of scope for UFGS 25 05 11 spec only. Contractor is directed to follow other specifications related to this topic.		
8	Proposed STIG and SRG Applicability Report	CM-2	Not Applicable	Out of scope for UFGS 25 05 11 spec only. Contractor is directed to follow other specifications related to this topic.		
	S	D-02 Shop Dra	wings			
1	Network Communication Report	CA-9, CM-6, CM-7, PL-8, SC-8, SC-41	Approved	Updated 7/26/22: Contractor provided submitto on 7/14/22. Information provided with the Cybersecurity Interconnection Schedule documents additional information needed for this report. Wireless communication was not identified in report. Wireless capability was reported as no requirement. (See Submittal 347.02-25 05 11). Contractor stated "Will Submit Later" on submittal package dated 4/12/22.		
2	Cybersecurity Riser Diagram	PL-2, PL-8	Approved			
		SD-03 Product	Data			
1	Control System Cybersecurity Documentation	SA-5	Approved	Updated 7/26/22: Contractor provided submitta on 7/14/22. Contractor stated "Will Submit Later" on submittal package dated 4/12/22.		
		SD-06 Test Rep	oorts			
1	Wireless Communication Test Report	AC-18	Not Submitted	Updated 7/26/22: Initially marked NA due the contractor reporting no wireless communications requirement (See Submittal 347.02-25 05 11). Wireless communication was recently discovered. Gov't will remediate after BOD. Physical device will be removed.		
2	Control System Cybersecurity Testing Procedures	RA-5	Not Applicable	Out of scope for UFGS 25 05 11 spec only. Contractor is directed to follow other specifications related to this topic.		






NAVFAC FRCS CyCx Checklist Example: Red Zone After Action Report

	NAVFAC FRCS Cybersecurity Co	mmissioning (CyCx) C	hecklist		
	Red Zone after	Action Report			
	(For Governme	ent Use Only)			
	Project or Work Order Number:			Cont	rol Sys
Contr	ol System or Device/Component (Choose one):			⊩-	Con
	Control System or Device/Component Name:			Cantrasta	
	Date:			Contracto	
Contractor	and government are required to completed listed action	no NAVEAC SE CIO ISSE will	document validation of	тето.	
	and government are required to completed listed action and not completed actions on this report. Actions not o			<u> </u>	IC-II-I
	oning (CyCx) Closeout memo.	ompicioa wiii be iistea on the r	1100 Cyborscounty	1 2	Collal
	Noteworthy	Strengths		3	Chris
1	Hotoworthy	Outinguio		5	Maria Joshu
2				Task ID	000110
3					_
4				_	Physi
5				ll .	JACE
Task ID	Action	Comments	ISSE's Validation	CA1	
	Contractor A	fter-Actions			
					Subm
				CA2	'Subn
					4/13/2
					NAVE
				GA1	Group
	Government A	fter-Actions			NAVF
				GA2	
				⊩—	NAVE
				GA3	applic
				GA3	contro
			-	I .	PWD
				GA4	1. Att
				ll .	Cybe
					PWD
				GA5	turno

NAVFAC FRCS Cybersecurity Commissioning (CyCx) Checklist								
		Action Report						
	(For Governm	ent Use Only)						
	Project or Work Order Number:	P4						
Conti	rol System or Device/Component (Choose one):	Control						
Control System or Device/Component Name: LCS Facility DDC								
Date: Friday, May 20, 2022								
Contractor and government are required to completed listed actions. NAVFAC SE CIO ISSE will document validation of completed								
	ompleted actions on this report. Actions not completed wi							
тето.								
	Noteworthy	Strenaths						
1	Collaboration between LCSRON 2, PWD Mayport,		Control.					
2	Lock down of physical access points to the control							
3	Chris (Johnson Controls) Control System subject n		lge of cybersecurity					
4	Maria Santos, Construction Manager, use of Flank	Speed Tools for team collab	poration (i.e., meetings,					
5	Joshua Fowler asking questions based on lessons	learned with turning over sy	stems to the BOSC.					
Task ID	Action	Comments	ISSE's Validation					
	Contractor A	After-Actions						
	Physically disable the wireless device on the JACE located in the 1st floor mechanical room.	Wireless communication was recently discovered. Only the wireless	Validation completed 7/26/22 by LouShawda Grant, 904-542-8404					
CA1		capabilities has been disable. Gov't will remediate after BOD.	304-342-0404					
	Submit remaining submittals listed on the	Remaining submittals	Validation completed 7/26/22					
CA2	'Submittal" tab. These submittals were expected at a later date as stated on transmittal #347 dated		by LouShawda Grant, 904-542-8404					
	4/13/2022. Government /	⊥ ∆fter-∆ctions						
GA1	NAVFAC SE CIO4 provide STIG training to Welsh Group and Johnson controls.	Bobby Kelly completed training on 7/25/22.	Validation completed 7/26/22 by LouShawda Grant, 904-542-8404					
GA2	NAVFAC SE CIO4 perform baseline scanning.	Bobby Kelly completed scanning. Results are at M:\CIO\CIO_2\ISSE\Mayp ort_P426_documents.	Validation completed 7/26/22 by LouShawda Grant, 904-542-8404					
GA3	NAVFAC SE CIO4 provide DoD User Banner application training to Welsh Group and Johnson controls.	Bobby Kelly completed training on 7/25/22.	Validation completed 7/26/22 by LouShawda Grant, 904-542-8404					
GA4	PWD Mayport locate transmittal #347 attachment 1. Attachment 1 was submitted as the Cybersecurity Interconnection Schedule.	Submitted and approved	Validation completed 7/26/22 by LouShawda Grant, 904-542-8404					
GA5	PWD Mayport schedule and communicate turnover date for DDC equipment.	Turnover date is set for 7/29/22. Laptop turned over on 6/27/22 to Joshua	Validation completed 7/26/22 by LouShawda Grant, 904-542-8404					



Close-Out Red Zone Commissioning Process





CyCx Close-out Memorandum

- Provides a close-out letter to the System Owner
- Addresses FRCS concerns related to residual risk and completion of commissioning
- Informs the System Owner of overall cybersecurity compliance prior to beneficial occupancy date (BOD)
- Provided to the Construction Manager for inclusion with Acceptance Testing Results

29 Jul 22

MEMORANDUM

From: NAVFAC Southeast Operational Technology Information System Security
Manager

To: Public Works Officer Mayport

Subj: Cybersecurity Commissioning (CyCx) Closeout of Direct Digital Control (DDC) System of Contract #N69450-19-C-0913 P426 LITTORAL COMBAT SHIP (LCS) SUPPORT FACILITY MAYPORT

Encl: (1) P426 LITTORAL COMBAT SHIP (LCS) FRCS Cybersecurity Commissioning Checklist

- 1. The DDC commissioned under the subject construction contract has been accepted by the Command Information Office (CIO) as of the Building Occupancy Date (BOD) of 30 July 2022. Approval representatives for the final commissioning validation:
 - a. LouShawda Grant, Cyber Design & CyCx SME, NAVFAC Southeast CIO2
 - b. Bobby Kelley, CyCx Technical Validator, NAVFAC Southeast CIO4
- 2. Enclosure (1) contains the Red Zone after Action Report final validation results of the Cybersecurity FRCS commissioning efforts in support of P426 LCS Support Facility.
- 3. During the cybersecurity commissioning validation review visit, active wireless communication was discovered. To minimize the risk, the wireless capabilities have been disabled. Government will assess the DDC's dependency on wireless communication after BOD.
- 4. Overall Cybersecurity compliance of the DDC is acceptable and meets the minimum requirement for integration into the base wide DDC boundary.

A. Jefferson



Red Zone CyCx Review

Red Zone Cybersecurity Commissioning (CyCx) is a method of evaluating whether the cybersecurity controls applied to a Facility Related Control System (FRCS) meet contract requirements using UFC and UFGS guides.

What Does Red Zone Cybersecurity Commissioning Accomplish?

- Helps determines what security controls are required by the contract and builds a CyCx Checklist specific to that contract
- Tracks Cybersecurity controls implementation through the use of the CyCx Checklist
- Provides an "After Action Report" after a Red Zone On-Site Assessment is performed
- Final Acceptance Testing is Performed in preparation for RZ close out
- Close Out Memo is provided to the System Owner at the end of the Red Zone Commissioning process outlining the overall cybersecurity contract compliance



Questions?

